Image Analysis Report

Generated: 2026-04-24 04:50:42Z | Source: corrosion.jpg | Report ID: 7ac40d57-6527-4187-b969-4546e5b1d455

Executive Summary

The image exhibits high severity corrosion characterized by significant localized material loss and advanced scaling. Degradation is heavily concentrated along a horizontal seam and a central focal point, suggesting a high risk to structural integrity and potential for through-wall penetration.

Key Findings

#	Finding
1	Severe localized pitting and exfoliating material loss at the center of the component.
2	Concentrated corrosion along a horizontal linear feature, indicative of preferential weld or crevice corrosion.
3	Extensive breakdown and total failure of the protective coating system across the visible area.
4	Presence of thick, friable rust scales indicating an active and long-term corrosion process.
5	Darker central regions suggest deep penetration that may exceed the design corrosion allowance.
6	Widespread atmospheric rust staining and surface bloom surrounding the primary defects.

Localized detections (VLM, approximate)

- Severe Scaling (conf. 92%): x=0.350, y=0.120, w=0.300, h=0.450
- Seam Corrosion (conf. 88%): x=0.000, y=0.460, w=1.000, h=0.100
- Widespread Corrosion (conf. 85%): x=0.000, y=0.100, w=1.000, h=0.850

Recommendations

#	Recommendation
1	Perform immediate Ultrasonic Testing (UT) spot and grid measurements to determine remaining wall thickness.
2	Conduct mechanical cleaning to SSPC-SP 11 (Power Tool Cleaning to Bare Metal) to assess the depth of pitting.
3	Initiate a Fitness-For-Service (FFS) assessment if the component is pressurized or load-bearing.
4	If wall loss exceeds the allowable limit, evaluate repair options such as weld overlay, flush patch, or composite wrapping.
5	Apply a high-performance multi-coat epoxy system following abrasive blast cleaning to SSPC-SP 10.
6	Establish a localized corrosion monitoring program with periodic NDT to track the degradation rate.